

USA 811 Positive Response Codes

1	Marked – Does conflict, underground facilities have been marked.
1A	Marked with Exceptions – High profile utility in conflict; utility owner will attempt to contact you to schedule site surveillance
1B	Marked with Exceptions – High-priority subsurface installation in conflict. Excavator MUST notify the member of the excavation or demolition start date and time.
2	Clear – No underground facilities are in the area where the excavation will take place.
3A	Unmarked – Locate technician could not gain access to property; call 811 to schedule access.
3B	Unmarked – Incorrect address information. Call 811 to verify the information on the ticket.
3C	Unmarked – Marking delay requested by locate technician and agreed to by excavator per agreement. Excavation site is unmarked. The locate technician cannot mark within two full working days. The excavator was contacted, and a new deadline was scheduled.
3D	Unmarked – Locate instructions are unclear. Call 811 to clarify where on the property you will be excavating and need the underground facilities located.
3E	Unmarked – The excavator has performed the excavation prior to the locator's arrival.
3F	Unmarked – Line is untonable and utility has been notified to resolve issue
4	Private Line – This is a private line and it is not the responsibility of the members of 811 to locate private facilities.